DISTRICT EMERGENCY OPERATION CENTER | UDMA RAPID INTELLIGENCE

NATIONAL DISASTER MANAGEMENT FRAMEWORK - SATELLITE SITREP

TARGET SECTOR: Texas Urban Tile · LEVIR-CD
REPORT DATE: 10 Oct 2026, 04:38 UTC
SENSOR / GSD: Aerial ortho · 0.5 m
OPERATION: Encroachment / planning audit

TOTAL IMPACT AREA	CRITICAL SITES (P1)	HIGH SEVERITY (P2)	TOTAL DETECTIONS
4,266 m²	5 Zones	5 Zones	16 Polygons

EXECUTIVE SITUATION SUMMARY:

Automated change-intelligence detected 16 change polygons totaling 4,266 m² across the surveyed bounds; 5 critical and 5 high-priority sites are queued for ground verification. 0.0% of the area was under cloud, shadow or no data on either date: not assessed, mapped separately. Detector: Track A · BIT (0.5 m aerial), F1 90% on LEVIR-CD test. High-priority footprints are available as draft SACHET-compatible CAP records.

PRIORITY TARGET AUDIT TABLE (TOP DETECTIONS):

ID	AREA (m²)	SEVERITY	CONFIDENCE	CLASSIFICATION	CENTROID (LAT, LON)
CHG_0005	424.6	Critical	95.2%	New Building / Structure	29.7636, -95.3784
CHG_0010	342.9	Critical	94.9%	New Building / Structure	29.7633, -95.3784
CHG_0008	331.0	Critical	95.1%	New Building / Structure	29.7633, -95.3777
CHG_0015	332.1	Critical	94.0%	New Building / Structure	29.7629, -95.3778
CHG_0006	283.4	Critical	94.9%	New Building / Structure	29.7636, -95.3777
CHG_0013	279.5	High	93.7%	New Building / Structure	29.7629, -95.3783

DATA LIMITATIONS:

- LEVIR-CD tiles carry no acquisition dates or coordinates: season, sun angle and comparability not assessed.
- Change dated only to the window between the two images: no yearly series stored for this area.
- Tile is not georeferenced: exposure and buffer checks not assessed.

RECOMMENDED IMMEDIATE DIRECTIVES:

1. Send Priority 1-2 sites for field verification in the case workflow.
2. Cross-check flagged sites against Development Plan, CRZ maps and building permissions.
3. Treat 'possible encroachment' as a screening flag, never as a legal finding.
4. Act only on field-confirmed cases; no demolition or eviction on satellite evidence alone.

Prepared By: T.R.A.C.E. Automated Remote Sensing System

Authorised Signatory / District Magistrate / Municipal Commissioner

Signature: _____ Date: _____