DISTRICT EMERGENCY OPERATION CENTER | UDMA RAPID INTELLIGENCE

NATIONAL DISASTER MANAGEMENT FRAMEWORK - SATELLITE SITREP

TARGET SECTOR: Mumbai Eastern Suburbs · Chembur-Ghatkopar **REPORT DATE:** 09 Oct 2026, 20:04 UTC

SENSOR / GSD: Sentinel-2 MSI · 10 m **OPERATION:** Encroachment / planning audit

TOTAL IMPACT AREA	CRITICAL SITES (P1)	HIGH SEVERITY (P2)	TOTAL DETECTIONS
75,487 m²	0 Zones	5 Zones	13 Polygons

EXECUTIVE SITUATION SUMMARY:

Automated change-intelligence detected 13 change polygons totaling 75,487 m² across the surveyed bounds; 0 critical and 5 high-priority sites are queued for ground verification. Cloud, shadow and no-data areas were not assessed and are mapped separately. Detector: Track B · Sentinel-2 spectral network, F1 22% on OSCD, leave-one-city-out. High-priority footprints are available as draft SACHET-compatible CAP records.

PRIORITY TARGET AUDIT TABLE (TOP DETECTIONS):

ID	AREA (m²)	SEVERITY	CONFIDENCE	CLASSIFICATION	CENTROID (LAT, LON)
CHG_0013	18,774.3	High	98.4%	Vegetation Cleared / Possible Co	19.0380, 72.9407
CHG_0007	3,111.6	High	89.3%	Water-body Encroachment	19.0750, 72.9423
CHG_0008	2,810.6	High	88.7%	Water-body Encroachment	19.0690, 72.9438
CHG_0005	6,423.9	High	93.3%	Water-body Encroachment	19.0798, 72.9334
CHG_0002	4,717.3	High	99.0%	Vegetation Cleared / Possible Co	19.0910, 72.9194
CHG_0001	11,943.5	Medium	98.7%	Vegetation Cleared / Possible Co	19.0948, 72.9215

RECOMMENDED IMMEDIATE DIRECTIVES:

1. Send Priority 1-2 sites for field verification in the case workflow.
2. Cross-check flagged sites against Development Plan, CRZ maps and building permissions.
3. Treat 'possible encroachment' as a screening flag, never as a legal finding.
4. Act only on field-confirmed cases; no demolition or eviction on satellite evidence alone.

Prepared By: ChangeIntel AI Automated Remote Sensing System

Authorised Signatory / District Magistrate / Municipal Commissioner

Signature: _____ Date: _____